

JAMES COOK UNIVERSITY
CYCLONE STRUCTURAL TESTING STATION

INVESTIGATION OF DIAPHRAGM ACTION OF CEILINGS

© James Cook University of North Queensland 1981

ISBN 0 86443 087 6

ISSN 0158 - 8338

Walker, George R. (George Redvers), 1938-
Investigation of diaphragm action of ceilings.
Progress report 2.

1. Ceilings. 2. Wind-pressure. I. Boughton, G.N.
(Geoffrey N.), 1954- . II. Gonano, David, 1959- .
III. James Cook University of North Queensland;
Cyclone Testing Station. IV. Title. (Series:
Technical report (James Cook University of North
Queensland. Cyclone Testing Station); 15).

PREFACE

It should be noted that this progress report is a summary of interim test results obtained as part of an extensive research programme. The authors believe that it is of benefit to the building industry to publish their findings in this manner, but stress that any conclusions drawn from these tests should be considered to be interim until the final report is published. Whilst it is unlikely that subsequent



INVESTIGATION OF DIAPHRAGM ACTION OF CEILINGS

- PROGRESS REPORT 2

George R. Walker

Geoffrey N. Boughton

David Gonano

SYNOPSIS

The Department of Civil and Systems Engineering at James Cook University of North Queensland and the James Cook Cyclone Structural Testing Station are currently engaged in a major joint program of research related to the transmission of wind forces in domestic housing.

One of the major projects within this program is a study of the capacity of the ceiling structure to transmit horizontal forces from the external walls to the bracing walls by diaphragm action. This project, which is being undertaken within the Department of Civil and Systems Engineering, with assistance from the Cyclone Testing Station, is being supported by the Australian Housing Research Council.


This report describes the results of the second phase of tests on ceiling panel assemblies undertaken as part of this project. Twelve tests are described, nine on plasterboard ('Gyprock') ceiling systems and three on fibre cement ('Versilux') systems. The systems are considered representative of many of the systems used in domestic housing. The size of panels tested and the testing procedure were similar to those used in the first

1. INTRODUCTION

This is the second interim report on a research project funded by the Australian Housing Research Council which is focused on the action of ceilings


2. EXPERIMENTAL PROCEDURE

The ceiling panels were tested in the same manner as those in the first phase -i.e. as shear walls using the University Wall Testing Machine.



4.

2700



TESTERS	BATTENS		JOIST SPACING mm	ULTIMATE LOAD kN	EQUIVALENT DESIGN LOAD kN/m	EQUIVALENT DESIGN STIFFNESS kN/mm	COMMENTS
	Spacing mm	Material	Spacing mm				
150 perim. 200 centre. 300		Pine	450	12.0	1.71	-	
300		Pine	450	3.6	0.51	0.55*	*Estimated
300		CSR Furring ch.	450	1.1	0.16	-	
300		-	-	5.2	0.74	0.84	Fixed directly to joists
150 perim 200 centre		-	-	6.0	0.85	0.80	Fixed directly to joists
150 perim 200 centre		Pine	450	5.6	0.80	0.51	
150 perim 200 centre		Pine	450	12.7	1.81	1.31	Edge battens nailed to top plates

Table 1 Summary of Test Results

CLADDING Material	FASTENERS		BATTENS		JOIST SPACING mm	ULTIMATE LOAD kN/m	EQUIVALENT DESIGN LOAD kN/m	EQUIVALENT DESIGN STIFFNESS kN/mm	COMMENTS
	Type	Spacing mm	Materials	Spacing mm					
rock mm	3 x 2700 x 1200	8.18 x 25 Hi-Lo Type S Screws	300	Pine	450	790	1.14	1.24	Gap at edge of sheet filled with plaster
rock mm	2 x 2700 x 1200	6.2 x 25 Bugle Head Tek Screws	300	CSR Furring ch. Pine	450	790	0.64	0.27	Gap at edge of sheet filled with plaster
rock mm	2 x 2700 x 1200	8.18 x 25 Hi-Lo Type S Screws	300	-	450	790	0.85	1.04	Nogging at edges
rock mm	2 x 2400 x 1350	8.18 x 25 Hi-Lo Type S Screws and glue	Screw 270 270 225	-	-	395	0.88	0.87	Glued and Screwed direct- ly to joists
rock mm	2 x 2700 x 1200	6.2 x 25 Bugle Head Tek Screws	300	Lysaght steel battens	450	790	0.64	0.60	Battens pierce fixed to joists
rock mm	2 x 2400 x 1350	8.18 x 30 Hi-Lo Type S Screws	265	-	-	395	0.97	0.99	Fixed directly to joists
rock mm	2 x 2400 x 1350	8.18 x 30 Hi-Lo Type S Screws	265	-	-	395	0.81	0.70	Fixed directly to joists
rock mm	2 x 2700 x 1200	8.18 x 30 Hi-Lo Type S Screws	300	Pine	450	900	0.53	0.63	


Table 1 Summary of Test Results

(continued)

of undetermined deflections at large loads and even estimate deflections at

recommended 30 mm long screws).

An increase of 120 percent in the ultimate load capacity was obtained and a



radius of each sheet of cladding. Test 10 was undertaken to determine the

ing channels to the ceiling joists to satisfactorily transmit the force.

least of the order of thirty to forty percent. The inconsistency is greater

previous test with 'versilux' cladding, and in which the cladding was attached to pine battens and to noggings between the battens along the edges of the


~~versilux sheets. Both the strength and stiffness were similar to the previous~~

alent plasterboard tests -i.e. with the plasterboard fixed directly to the ceiling joists.

The test suggests that this system is adequate for W42 construction providing bracing walls are restricted to a maximum spacing of 6.5 m and the internal building width is not less than 7 m.

4.2.2 Test 6

This confirms the opinion given following Test 1 based on observed distress of cladding fasteners that the panel was close to failure due to pull through of the cladding fasteners when the batten/ceiling joist connection failure occurred. It also confirmed that noggining between the battens along








Figure 3 Load - Deflection Curve for a Single Fastener
Loaded in-plane of the Sheeting.

of the system under test. This can be appreciated when the failure patterns

broken pieces of sheeting

tear in sheeting








Figure 7 Deflections of Fasteners in Sheeting during the Transition Portion of the Test





Figure 8 Bearing of Gap Fill Material along the Compression Diagonal

ing away from the sheeting through an edge, causes load on the remaining fasteners to change in both magnitude and direction. Thus the load - deflection curve for a particular fastener changes due to load redistribution as tests proceed. Typically characteristics change from those shown in figure 4(ii) towards those shown in figure 4(iii) which tends to prolong the plastic portion of the panel load - deflection curve.


At the failure point, failure of one fastener and subsequent load redistribu-


Some general conclusion are:


- . systems in which the cladding is directly attached to the ceiling



- A - Gyprock and Versilux direct to joists as per Tests 13 and 5 respectively
- B - Versilux on timber battens as per Test 6
- C - Gyprock on timber battens as per Test 15
- D - Versilux on timber battens and nogging as per Test 7
- E - Gyprock on timber battens as per Test 13
- F - Gyprock on timber battens as per Test 14








8. REFERENCES

1. Walker, G.R. and Gonano, D. Investigation of Diaphragm Action of Ceilings - Progress Report 1. Technical Report No. 10, James Cook Cyclone Structural Testing Station, November, 1981.
2. Guidelines for Cyclone Product Testing and Evaluation. Technical Record 440, Experimental Building Station, Sydney, 1977.


APPENDIX
DETAILS OF TESTS

A.1 TEST 4

A.1.1 Test Panel



28.



were fastened perpendicular to the ceiling joists using 25 x 1.8 mm Flex Sheet
rails at 150 mm spacing around the perimeter of each sheet and 200 mm spacing




Figure A.3 Test Panel 5






Figure A.4 Load - Deflection Curve Test 5



A.3.2. Test Results



A.4.3 Test Results

The panel failed at a load of 12.7 kN as a result of the fasteners pulling through the cladding. The observed load - deflection behaviour of the panel is shown in figure A.8. The effect of nailing the end battens to the top plate as well as the joists was to restrict the relative displacement between the battens and joists to less than 5 mm.

Little rotation of the individual cladding elements occurred due to the small displacement of the battens relative to the ceiling joists.

A.5 TEST 8

A.5.1 Test Panel

In this test two 2900 x 1200 x 10 mm 'Gyprock' sheets were fixed perpendicular to the timber battens. The gap between the end of the sheets and the top plate was filled with plaster cement (figure A.9).

The panel geometry for this test was as follows:

distance between top plates	2815 mm
spacing of ceiling joists	800 mm

for floor

furring channel or timber batten

A.5.3 Test Results




Figure A.11 Crushing of Plasterboard and Gap Fill Material






Figure A.12 Load - Deflection Curve Test 8




top plate

nogging

extra screw per nogging




41.



The panel geometry for this test was as follows:

distance between top plates	2815 mm
spacing of ceiling joists	400 mm


1000 20 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100



2.8 kN, unloaded, and then relaoded in slightly larger load increments to failure.

A.9.3 Test Results

The panel failed at a load of 4.5 kN as a result of the fasteners pulling through the cladding. The observed load - deflection behaviour is shown in figure A.19. The end battens showed no displacement relative to the ceiling joist. The entire cladding rotated as a single unit. It was observed that the fasteners closest to the loading point were






Figure A.20 Test Panels 13 and 14

7
(k)
6

A.10.3 Test Results

The panel failed at a load of 6.75 kN as a result of the fasteners pulling through the cladding. The observed load - deflection behaviour of the panel is shown in figure A.21. The entire cladding rotated as a single unit.

A.11 TEST 14

A.11.1 Test Panel


Test panel 14 was identical to the panel used in Test 13 (figure A.20).

A.11.2 Loading Pattern

The panel was loaded in increments of approximately 0.5 kN up to a load of 2.2 kN, unloaded, and then reloaded to failure in slightly larger load increments.

A.11.3 Test Results

The observed load - deflection behaviour of the panel is shown in figure A.22. Failure occurred at a load of 5.1 kN as a result of fasteners pulling through the cladding. The cladding rotated as a single unit with the recessed joint






Figure 22 Load Deflection Curve

2.2 kN, unloaded and then reloaded to failure.

A.12.3 Test Results

The panel failed at a load of 3.75 kN as a result of fasteners pulling through the cladding. The observed load - deflection curve is shown in figure A.23. The entire cladding rotated as a single unit. There was no relative displacement between the timber battens and the ceiling joists.